Runway 29 Existing Obstruction Table
Inner Portion of the Approach Surface

Object ID	Description	Object Elevation (MSL)	Part 77 Approach		Departure Surface		Threshold Siting Surface		VGS Surface		PAPI		TERPS Visual Surface		Disposition
			Surface Elevation (MSL)	Penetration/ Clearance (ft)	Surface Elevation (MSL)	Penetration/ Clearance (ft)	Surface Elevation (MSL)	Penetration/ Clearance (ft)	Surface Elevation (MSL)	Penetration/ Clearance (ft)	Surface Elevation (MSL)	Penetration/ Clearance (ft)	Surface Elevation (MSL)	Penetration/ Clearance (ft)	
600	Tree	609.6	615.0	-5.4	635.0	-25.4	643.1	-33.5	661.5	-51.9	643.1	-33.5	694.0	-84.4	No Action
601	Building	611.1	-	-	645.5	-34.4	-	-	-	-	-	-	-	-	No Action
603	Tree	615.7	615.1	0.6	635.2	-19.5	643.3	-27.6	-	-	-	-	-	-	Airspace Study/Removal
604	Tree	612.2	615.6	-3.5	635.8	-23.6	644.1	-31.9	-	-	-	-	-	-	No Action
605	Tree	659.7	615.7	44.0	635.9	23.8	644.2	15.5	-	-	-	-	-	-	Airspace Study/Removal
606	Building	607.1	615.7	-8.6	635.9	-28.8	644.2	-37.1	-	-	-	-	-	-	No Action
607	Light Pole	609.1	615.9	-6.8	636.2	-27.1	-	-	-	-	-	-	-	-	No Action
608	Tree	614.8	616.4	-1.6	636.7	-21.9	645.2	-30.4	-	-	-	-	-	-	Airspace Study/Removal
611	Tree	643.5	616.6	26.9	637.0	6.5	-	-	-	-	-	-	-	-	Airspace Study/Removal
612	Tree	628.5	616.6	11.9	637.0	-8.5	645.5	-17.0	-	-	645.5	-17.0	696.6	-68.1	Airspace Study/Removal
614	Utility Pole	617.4	616.8	0.6	637.3	-19.9	645.8	-28.4	-	-	-	-	696.9	-79.5	Airspace Study/Removal
615	Tree	630.7	616.8	13.9	637.3	-6.5	645.8	-15.1	-	-	-	-	696.9	-66.2	Airspace Study/Removal
616	Building	610.7	616.9	-6.2	637.3	-26.6	-	-	-	-	-	-	-	-	No Action
617	Tree	645.8	-	-	646.0	-0.1	-	-	-	-	-	-	-	-	No Action
619	Tree	649.3	617.1	32.2	637.7	11.7	-	-	-	-	-	-	-	-	Airspace Study/Removal
620	Tree	609.6	617.1	-7.5	637.7	-28.0	646.3	-36.6	-	-	-	-	-	-	No Action
622	Tree	653.1	617.3	35.8	637.9	15.2	646.5	6.5	-	-	-	-	-	-	Airspace Study/Removal
624	Tree	638.2	617.4	20.8	638.1	0.1	-	-	-	-	-	-	-	-	Airspace Study/Removal
625	Tree	608.8	617.5	-8.7	638.2	-29.3	646.8	-38.0	-	-	-	-	-	-	No Action
626	Tree	662.6	617.7	44.9	638.4	24.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
628	Building	609.0	617.8	-8.8	638.5	-29.5	647.3	-38.3	666.2	-57.2	647.3	-38.3	698.5	-89.5	No Action
629	Building	609.9	617.8	-7.9	638.5	-28.6	647.3	-37.3	-	-	-	-	-	-	No Action
630	Tree	641.1	618.0	23.1	638.8	2.3	-	-	-	-	-	-	-	-	Airspace Study/Removal
631	Tree	611.9	618.2	-6.3	639.0	-27.1	-	-	-	-	-	-	-	-	No Action
632	Tree	640.7	618.2	22.5	639.0	1.7	647.9	-7.2	-	-	-	-	-	-	Airspace Study/Removal
633	Tree	639.1	-	-	646.1	-6.9	-	-	-	-	-	-	-	-	No Action
634	Tree	622.9	618.3	4.6	639.2	-16.2	648.1	-25.1	667.1	-44.2	648.1	-25.1	699.4	-76.4	Airspace Study/Removal
635	Tree	648.2	-	-	660.8	-12.6	-	-	-	-	-	-	-	-	No Action
637	Tree	646.4	618.5	28.0	639.4	7.1	648.3	-1.8	667.4	-20.9	648.3	-1.8	699.6	-53.2	Airspace Study/Removal
639	Tree	611.2	618.6	-7.4	639.5	-28.3	648.5	-37.3	-	-	-	-	699.8	-88.6	No Action
640	Tree	618.0	618.7	-0.7	639.6	-21.6	648.5	-30.6	667.6	-49.7	648.5	-30.6	699.9	-81.9	No Action
641	Tree	622.3	618.7	3.6	639.6	-17.3	648.6	-26.3	667.7	-45.4	648.6	-26.3	699.9	-77.6	Airspace Study/Removal
642	Tree	657.1	618.7	38.5	639.6	17.5	-	-	-	-	-	-	-	-	Airspace Study/Removal
643	Tree	626.2	618.7	7.5	639.7	-13.5	648.6	-22.4	-	-	648.6	-22.4	700.0	-73.8	Airspace Study/Removal
644	Tree	644.5	618.7	25.8	639.7	4.9	648.6	-4.1	-	-	-	-	-	-	Airspace Study/Removal
645	Tree	643.6	618.8	24.9	639.7	3.9	-	-	-	-	-	-	-	-	Airspace Study/Removal
646	Tree	644.3	-	-	647.1	-2.8	-	-	-	-	-	-	-	-	No Action
647	Tree	643.9	618.9	25.0	639.9	4.0	648.9	-5.0	668.1	-24.2	648.9	-5.0	700.3	-56.4	Airspace Study/Removal
648	Tree	663.1	619.0	44.1	640.0	23.1	-	-	-	-	-	-	-	-	Airspace Study/Removal
649	Tree	620.3	619.1	1.2	640.1	-19.8	649.2	-28.8	-	-	649.2	-28.8	700.5	-80.2	Airspace Study/Removal
651	Tree	646.3	619.4	26.9	640.5	5.8	649.6	-3.3	668.8	-22.6	649.6	-3.3	701.0	-54.8	Airspace Study/Removal
652	Tree	638.6	619.4	19.2	640.5	-1.9	649.6	-11.0	-	-	-	-	701.1	-62.4	Airspace Study/Removal
653	Tree	675.9	619.4	56.4	640.6	35.3	-	-	-	-	-	-	-	-	Airspace Study/Removal
655	Tree	615.9	619.5	-3.6	640.6	-24.7	649.8	-33.8	669.1	-53.1	649.8	-33.8	701.2	-85.3	No Action
656	Road Sign	614.2	619.5	-5.3	640.7	-26.5	649.8	-35.6	-	-	-	-	-	-	No Action
657	Tree	633.0	619.6	13.4	640.8	-7.7	-	-	-	-	-	-	-	-	Airspace Study/Removal
658	Tree	628.4	619.7	8.8	640.8	-12.4	650.0	-21.6	-	-	-	-	701.5	-73.0	Airspace Study/Removal
659	Tree	628.1	619.7	8.4	640.9	-12.8	-	-	-	-	-	-	-	-	Airspace Study/Removal
661	Tree	654.2	619.8	34.4	641.0	13.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
662	Tree	616.6	619.8	-3.1	641.0	-24.4	650.2	-33.6	-	-	-	-	-	-	No Action
663	Tree	654.6	619.9	34.8	641.1	13.5	-	-	-	-	-	-	-	-	Airspace Study/Removal
664	Tree	632.5	620.0	12.5	641.2	-8.7	650.5	-18.0	669.8	-37.3	650.5	-18.0	702.0	-69.5	Airspace Study/Removal
665	Tree	649.3	620.0	29.4	641.2	8.1	-	-	-	-	-	-	-	-	Airspace Study/Removal
666	Tree	614.7	620.0	-5.3	641.2	-26.6	No Action		650.5	-35.8	-	-	702.0	-87.3	No Action
667	Tree	617.4	620.0	-2.6	641.3	-23.9	650.5	-33.1	-	-	-	-	-	-	No Action
668	Tree	629.8	620.1	9.7	641.4	-11.6	650.7	-20.8	670.1	-40.2	650.7	-20.8	702.2	-72.4	Airspace Study/Removal
669	Tree	636.9	620.1	16.8	641.4	-4.5	650.7	-13.7	670.1	-33.1	650.7	-13.7	702.2	-65.3	Airspace Study/Removal
671	Tree	640.2	-	-	641.9	-1.7	-	-	-	-	-	-	-	-	No Action
672	Tree	617.9	620.2	-2.3	641.6	-23.6	-	-	-	-	-	-	-	-	No Action
673	Tree	654.1	620.2	33.8	641.6	12.5	-	-	-	-	-	-	-	-	Airspace Study/Removal
674	Tree	611.9	620.3	-8.4	641.6	-29.7	650.9	-39.0	670.4	-58.4	650.9	-39.0	702.5	-90.5	No Action
675	Tree	649.1	620.3	28.9	641.6	7.5	-	-	-	-	-	-	-	-	Airspace Study/Removal
676	Tree	658.5	620.3	38.1	641.7	16.8	-	-	-	-	-	-	-	-	Airspace Study/Removal
677	Building	610.4	620.3	-9.9	641.7	-31.3	651.0	-40.6	-	-	651.0	-40.6	702.6	-92.1	No Action
678	Tree	618.2	620.4	-2.2	641.8	-23.6	-	-	-	-	-	-	-	-	No Action
679	Utility Pole	615.1	620.4	-5.3	641.8	-26.7	651.2	-36.0	-	-	-	-	702.7	-87.6	No Action
680	Tree	618.7	620.6	-1.9	642.0	-23.3	651.4	-32.7	670.8	-52.2	651.4	-32.7	702.9	-84.3	No Action
681	Tree	613.1	620.7	-7.5	642.1	-28.9	651.5	-38.3	-	-	-	-	703.1	-89.9	No Action
682	Tree	620.1	620.7	-0.5	642.1	-22.0	-	-	-	-	-	-	-	-	No Action
683	Tree	653.8	620.7	33.2	642.1	11.7	-	-	-	-	-	-	-	-	Airspace Study/Removal
686	Tree	619.8	620.8	-1.0	642.3	-22.4	-	-	-	-	-	-	-	-	No Action
687	Tree	643.6	620.8	22.8	642.3	1.3	-	-	-	-	-	-	-	-	Airspace Study/Removal
688	Building	616.2	620.9	-4.6	642.3	-26.1	651.8	-35.6	671.3	-55.1	651.8	-35.6	703.4	-87.2	No Action
690	Tree	616.6	621.0	-4.4	642.5	-25.9	651.9	-35.4	671.5	-54.9	651.9	-35.4	703.6	-87.0	No Action
691	Tree	634.0	621.0	13.0	642.5	-8.5	652.0	-17.9	671.5	-37.5	652.0	-17.9	703.6	-69.6	Airspace Study/Removal
692	Tree	633.6	621.0	12.7	642.5	-8.9	-	-	-	-	-	-	-	-	Airspace Study/Removal
693	Tree	640.3	-	-	651.4	-11.0	-	-	-	-	-	-	-	-	No Action
694	Utility Pole	615.7	621.3	-5.6	642.8	-27.2	652.4	-36.7	-	-	-	-	704.0	-88.4	No Action
697	Tree	615.0	621.6	-6.6	643.3	-28.3	652.9	-37.9	672.6	-57.6	652.9	-37.9	704.6	-89.6	No Action
698	Tree	623.2	621.7	1.5	643.4	-20.2	653.0	-29.8	-	-	653.0	-29.8	704.7	-81.5	Airspace Study/Removal
699	Tree	613.5	621.7	-8.3	643.4	-30.0	-	-	-	-	-	-	-	-	No Action
701	Tree	659.9	-	-	644.0	15.9	-	-	-	-	-	-	-	-	Airspace Study/Removal
702	Tree	614.3	622.0	-7.7	643.7	-29.5	-	-	-	-	-	-	-	-	No Action
703	Tree	620.2	622.2	-1.9	644.0	-23.8	653.7	-33.5	673.5	-53.3	653.7	-33.5	705.5	-85.3	No Action
704	Tree	631.1	622.2	8.9	644.1	-12.9	653.8	-22.7	-	-	-	-	705.6	-74.5	Airspace Study/Removal
705	Tree	613.3	622.3	-9.0	644.1	-30.8	-	-	-	-	-	-	-	-	No Action
707	Utility Pole	616.9	622.3	-5.4	644.1	-27.3	653.9	-37.0	673.7	-56.8	653.9	-37.0	705.7	-88.8	No Action
708	Tree	614.7	622.4	-7.7	644.2	-29.5	654.0	-39.3	-	-	654.0	-39.3	705.8	-91.1	No Action
709	Tree	628.3	622.5	5.8	644.4	-16.0	654.1	-25.8	-	-	-	-	706.0	-77.7	Airspace Study/Removal
710	Tree	635.6	622.5	13.1	644.4	-8.7	654.2	-18.5	-	-	-	-	-	-	Airspace Study/Removal
711	Tree	633.7	622.6	11.2	644.5	-10.7	654.3	-20.5	-	-	-	-	706.1	-72.4	Airspace Study/Removal
712	Tree	649.8	-	-	658.7	-8.9	-	-	-	-	-	-	-	-	No Action
713	Antenna	622.0	622.7	-0.7	644.6	-22.7	654.5	-32.5	674.4	-52.4	654.5	-32.5	706.3	-84.3	No Action
714	Tree	615.9	622.7	-6.9	644.7	-28.8	-	-	-	-	-	-	-	-	No Action
715	Tree	648.7	622.8	25.9	644.7	3.9	654.6	-5.9	-	-	-	-	-	-	Airspace Study/Removal
716	Tree	620.9	622.8	-1.9	644.8	-23.9	654.7	-33.8	-	-	-	-	706.6	-85.6	No Action
717	Tree	642.6	622.9	19.7	644.8	-2.3	654.7	-12.2	-	-	-	-	706.6	-64.0	Airspace Study/Removal
718	Light Pole	620.4	622.9	-2.4	644.9	-24.4	-	-	-	-	-	-	-	-	No Action
719	Tree	639.7	622.9	16.8	644.9	-5.2	654.8	-15.0	-	-	-	-	706.7	-66.9	Airspace Study/Removal
721	Tree	641.1	-	-	651.2	-10.1	-	-	-	-	-	-	-	-	No Action
722	Tree	626.5	623.2	3.3	645.3	-18.8	655.3	-28.8	-	-	-	-	707.2	-80.7	Airspace Study/Removal
723	Tree	647.9	623.2	24.7	645.3	2.6	655.3	-7.3	-	-	-	-	707.2	-59.3	Airspace Study/Removal
724	Tree	630.2	623.2	6.9	645.3	-15.1	655.3	-25.1	675.3	-45.1	655.3	-25.1	707.2	-77.0	Airspace Study/Removal
725	Tree	648.9	623.3	25.5	645.4	3.4	655.4	-6.5	-	-	-	-	-	-	Airspace Study/Removal
727	Tree	652.2	623.4	28.8	645.5	6.7	655.5	-3.3	-	-	-	-	-	-	Airspace Study/Removal
729	Billboard	641.3	623.5	17.8	645.7	-4.4	655.7	-14.4	-	-	655.7	-14.4	707.7	-66.3	Airspace Study/Removal
731	Tree	637.5	623.7	13.8	645.9	-8.4	-	-	-	-	-	-	-	-	Airspace Study/Removal
732	Tree	631.7	623.7	7.9	645.9	-14.3	656.0	-24.3	-	-	-	-	-	-	Airspace Study/Removal
733	Tree	647.5	623.7	23.7	645.9	1.5	-	-	-	-	-	-	-	-	Airspace Study/Removal
734	Tree	647.3	624.1	23.2	646.3	1.0	-	-	-	-	-	-	-	-	Airspace Study/Removal
735	Tree	639.3	624.1	15.2	646.4	-7.1	656.6	-17.2	676.7	-37.4	656.6	-17.2	708.6	-69.2	Airspace Study/Removal
736	Building	616.7	624.2	-7.5	646.5	-29.8	656.6	-40.0	676.8	-60.2	656.6	-40.0	708.7	-92.0	No Action
738	Utility Pole	631.3	624.2	7.1	646.6	-15.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
739	Tree	636.2	624.3	11.9	646.6	-10.4	-	-	-	-	-	-	-	-	Airspace Study/Removal
740	Tree	640.5	624.3	16.2	646.6	-6.1	656.8	-16.3	677.0	-36.5	656.8	-16.3	708.9	-68.4	Airspace Study/Removal
741	Tree	637.7	624.3	13.3	646.7	-9.0	656.9	-19.2	677.1	-39.5	656.9	-19.2	709.0	-71.3	Airspace Study/Removal
743	Building	619.1	624.5	-5.4	646.9	-27.8	-	-	-	-	-	-	-	-	No Action
744	Tree	616.0	624.5	-8.5	646.9	-30.9	657.2	-41.2	-	-	-	-	-	-	No Action
746	Tree	655.7	-	-	670.2	-14.5	-	-	-	-	-	-	-	-	No Action
747	Tree	639.9	624.7	15.2	647.2	-7.3	657.5	-17.5	677.8	-37.9	657.5	-17.5	709.6	-69.7	Airspace Study/Removal
748	Tree	654.0	624.8	29.2	647.2	6.7	-	-	-	-	-	-	-	-	Airspace Study/Removal
749	Light Pole	628.9	624.9	4.0	647.4	-18.5	657.7	-28.8	-	-	657.7	-28.8	709.9	-81.0	Airspace Study/Removal
750	Light Pole	650.5	625.0	25.5	647.5	2.9	657.9	-7.4	-	-	-	-	-	-	Airspace Study/Removal
751	Tree	644.9	625.1	19.8	647.7	-2.7	-	-	-	-	-	-	-	-	Airspace Study/Removal
752	Tree	649.4	625.2	24.2	647.8	1.7	-	-	-	-	-	-	-	-	Airspace Study/Removal
753	Tree	638.4	625.2	13.2	647.8	-9.4	658.2	-19.8	678.6	-40.2	658.2	-19.8	710.4	-72.0	Airspace Study/Removal
754	Utility Pole	621.5	625.3	-3.8	647.9	-26.4	658.3	-36.8	678.7	-57.2	658.3	-36.8	710.4	-88.9	No Action
756	Tree	655.0	-	-	657.8	-2.8	-	-	-	-	-	-	-	-	No Action
757	Tree	667.0	-	-	679.3	-12.2	-	-	-	-	-	-	-	-	No Action
758	Tree	644.5	-	-	648.2	-3.7	-	-	-	-	-	-	-	-	No Action
759	Building	621.1	625.5	-4.4	648.2	-27.1	658.6	-37.5	679.1	-58.0	658.6	-37.5	710.9	-89.8	No Action
760	Utility Pole	621.8	625.6	-3.9	648.3	-26.5	658.8	-37.0	679.2	-57.5	658.8	-37.0	711.0	-89.2	No Action
761	Tree	653.8	625.7	27.9	648.4	5.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
762	Building	619.4	625.7	-6.4	648.4	-29.1	-	-	-	-	-	-	-	-	No Action
763	Tree	640.1	625.8	14.3	648.5	-8.4	-	-	-	-	-	-	-	-	Airspace Study/Removal
764	Tree	670.5	-	-	681.4	-10.9	-	-	-	-	-	-	-	-	No Action
765	Tree	648.6	-	-	648.7	-0.1	-	-	-	-	-	-	-	-	No Action
766	Tree	671.0	626.0	45.0	648.8	22.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
767	Tree	672.9	-	-	666.2	6.7	-	-	-	-	-	-	-	-	Airspace Study/Removal
768	Light Pole	649.1	626.3	22.8	649.1	0.0	659.8	-10.7	-	-	659.8	-10.7	712.1	-63.0	Airspace Study/Removal
769	Tree	669.2	-	-	676.4	-7.1	-	-	-	-	-	-	-	-	No Action
770	Tree	659.8	-	-	655.1	4.7	-	-	-	-	-	-	-	-	Airspace Study/Removal
772	Tree	667.2	626.6	40.7	649.5	17.8	-	-	-	-	-	-	-	-	Airspace Study/Removal
773	Tree	665.6	626.7	38.9	649.7	15.9	-	-	-	-	-	-	-	-	Airspace Study/Removal
774	Tree	617.8	626.8	-9.0	649.7	-32.0	660.5	-42.7	681.2	-63.4	660.5	-42.7	712.9	-95.1	No Action
775	Utility Pole	620.7	626.8	-6.1	649.8	-29.1	660.5	-39.8	681.2	-60.5	660.5	-39.8	712.9	-92.2	No Action
776	Tree	669.5	-	-	670.2	-0.7	-	-	-	-	-	-	-	-	No Action
777	Tree	662.2	-	-	659.5	2.7	-	-	-	-	-	-	-	-	Airspace Study/Removal
779	Utility Pole	635.5	627.2	8.3	650.3	-14.8	661.2	-25.6	-	-	-	-	-	-	Airspace Study/Removal
780	Tree	654.2	-	-	650.3	3.8	-	-	-	-	-	-	-	-	Airspace Study/Removal
781	Light Pole	651.6	627.3	24.3	650.4	1.2	661.3	-9.7	-	-	-	-	713.7	-62.1	Airspace Study/Removal
782	Tree	617.5	627.3	-9.8	650.4	-32.9	661.3	-43.8	682.1	-64.6	661.3	-43.8	713.7	-96.2	No Action
783	Tree	658.1	627.4	30.7	650.5	7.6	-	-	-	-	-	-	-	-	Airspace Study/Removal
786	Tree	664.9	627.6	37.4	650.7	14.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
788	Tree	628.1	627.6	0.5	650.8	-22.7	661.7	-33.6	682.6	-54.5	661.7	-33.6	714.2	-86.1	Airspace Study/Removal
789	Tree	659.0	-	-	654.0	4.9	-	-	-	-	-	-	-	-	Airspace Study/Removal
790	Tree	682.4	627.7	54.7	650.9	31.5	-	-	-	-	-	-	-	-	Airspace Study/Removal
791	Tree	687.0	627.8	59.2	651.0	36.0	-	-	-	-	-	-	-	-	Airspace Study/Removal
792	Tree	618.6	627.9	-9.2	651.1	-32.5	662.1	-43.4	-	-	-	-	714.6	-95.9	No Action
794	Tree	624.2	627.9	-3.8	651.2	-27.0	662.2	-38.0	683.1	-58.9	662.2	-38.0	714.7	-90.5	No Action
795	Tree	684.5	628.0	56.6	651.2	33.3	-	-	-	-	-	-	-	-	Airspace Study/Removal
796	Tree	660.3	-	-	658.2	2.1	-	-	-	-	-	-	-	-	Airspace Study/Removal
797	Utility Pole	627.1	628.1	-1.0	651.4	-24.3	662.4	-35.3	-	-	662.4	-35.3	714.9	-87.8	No Action
798	Tree	625.1	628.1	-3.0	651.4	-26.3	662.5	-37.4	683.5	-58.3	662.5	-37.4	715.0	-89.9	No Action
799	Tree	647.1	-	-	651.5	-4.4	-	-	-	-	-	-	-	-	No Action
800	Tree	684.6	-	-	690.1	-5.5	-	-	-	-	-	-	-	-	No Action
801	Building	619.1	628.3	-9.2	651.6	-32.5	-	-	-	-	-	-	-	-	No Action
802	Tree	672.5	628.3	44.2	651.6	20.9	-	-	-	-	-	-	-	-	Airspace Study/Removal
803	Tree	621.4	628.5	-7.0	651.8	-30.4	662.9	-41.5	684.0	-62.5	662.9	-41.5	715.5	-94.1	No Action
804	Tree	674.2	-	-	652.0	22.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
805	Light Pole	653.6	628.7	24.9	652.1	1.5	663.3	-9.7	-	-	663.3	-9.7	715.9	-62.3	Airspace Study/Removal
806	Tree	678.2	628.7	49.5	652.1	26.0	-	-	-	-	-	-	-	-	Airspace Study/Removal
807	Tree	678.1	628.7	49.4	652.2	25.9	-	-	-	-	-	-	-	-	Airspace Study/Removal
808	Tree	682.7	628.7	53.9	652.2	30.5	-	-	-	-	-	-	-	-	Airspace Study/Removal
809	Billboard	625.3	629.0	-3.7	652.5	-27.2	663.7	-38.4	-	-	663.7	-38.4	716.4	-91.1	No Action
810	Tree	679.1	629.3	49.8	652.9	26.1	-	-	-	-	-	-	-	-	Airspace Study/Removal
811	Tree	656.3	-	-	653.0	3.3	-	-	-	-	-	-	-	-	Airspace Study/Removal
812	Utility Pole	629.0	629.5	-0.5	653.2	-24.2	664.5	-35.5	-	-	664.5	-35.5	717.2	-88.3	No Action
813	Light Pole	653.6	629.6	24.0	653.3	0.3	664.6	-11.1	-	-	664.6	-11.1	717.4	-63.8	Airspace Study/Removal
814	Tree	645.6	629.7	15.9	653.4	-7.8	-	-	-	-	-	-	-	-	Airspace Study/Removal
815	Tree	670.6	629.8	40.8	653.6	17.0	-	-	-	-	-	-	-	-	Airspace Study/Removal
816	Light Pole	636.2	629.9	6.3	653.6	-17.4	665.0	-28.8	-	-	665.0	-28.8	717.8	-81.6	Airspace Study/Removal

Runway 29 Inner Approach (Existing)

Runway 29 Existing Obstruction Table
Inner Portion of the Approach Surface

Object ID	Description	Object Elevation (MSL)	Part 77 Approach		Departure Surface		Threshold Siting Surface		VGS Surface		PAPI		TERPS Visual Surface		Disposition
			Surface Elevation (MSL)	Penetration/ Clearance (ft)	Surface Elevation (MSL)	Penetration/ Clearance (ft)	Surface Elevation (MSL)	Penetration/ Clearance (ft)	Surface Elevation (MSL)	Penetration/ Clearance (ft)	Surface Elevation (MSL)	Penetration/ Clearance (ft)	Surface Elevation (MSL)	Penetration/ Clearance (ft)	
817	Tree	642.7	629.9	12.8	653.6	-11.0	-	-	-	-	-	-	-	-	Airspace Study/Removal
818	Tree	685.9	-	-	700.7	-14.8	-	-	-	-	-	-	-	-	No Action
819	Tree	659.6	630.3	29.3	654.2	5.4	-	-	-	-	-	-	-	-	Airspace Study/Removal
821	Utility Pole	644.2	630.4	13.8	654.2	-10.0	665.8	-21.6	-	-	-	-	-	-	Airspace Study/Removal
822	Tree	660.6	-	-	654.3	6.3	-	-	-	-	-	-	-	-	Airspace Study/Removal
823	Tree	666.5	-	-	654.6	11.9	-	-	-	-	-	-	-	-	Airspace Study/Removal
824	Light Pole	658.8	630.7	28.1	654.6	4.1	666.2	-7.5	-	-	-	-	-	-	Airspace Study/Removal
825	Tree	658.0	630.8	27.2	654.8	3.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
826	Light Pole	654.6	630.9	23.7	654.9	-0.3	666.5	-11.9	-	-	666.5	-11.9	719.4	-64.8	Airspace Study/Removal
827	Tree	662.2	-	-	655.0	7.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
828	Building	634.1	-	-	655.0	-20.9	-	-	-	-	-	-	-	-	No Action
829	Building	637.3	631.1	6.2	655.1	-17.9	-	-	-	-	-	-	-	-	Airspace Study/Removal
830	Tree	652.3	631.1	21.2	655.1	-2.8	-	-	-	-	-	-	-	-	Airspace Study/Removal
832	Building	636.7	631.3	5.4	655.3	-18.7	-	-	-	-	-	-	-	-	Airspace Study/Removal
833	Tree	680.6	-	-	655.6	25.0	-	-	-	-	-	-	-	-	Airspace Study/Removal
834	Tree	659.2	631.6	27.6	655.7	3.4	-	-	-	-	-	-	-	-	Airspace Study/Removal
835	Tree	627.3	631.6	-4.3	655.8	-28.5	667.5	-40.3	-	-	-	-	720.5	-93.3	No Action
837	Tree	650.5	631.6	18.9	655.8	-5.3	-	-	-	-	-	-	-	-	Airspace Study/Removal
838	Tree	674.5	-	-	657.0	17.5	-	-	-	-	-	-	-	-	Airspace Study/Removal
840	Tree	652.9	631.9	21.0	656.2	-3.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
841	Tree	625.4	631.9	-6.6	656.2	-30.8	668.1	-42.7	-	-	-	-	721.1	-95.7	No Action
842	Light Pole	655.5	632.0	23.5	656.3	-0.8	668.1	-12.6	-	-	668.1	-12.6	721.2	-65.7	Airspace Study/Removal
843	Tree	669.4	-	-	656.3	13.1	-	-	-	-	-	-	-	-	Airspace Study/Removal
844	Building	635.1	-	-	656.5	-21.4	-	-	-	-	-	-	-	-	No Action
845	Tree	661.8	632.2	29.6	656.5	5.2	-	-	-	-	-	-	-	-	Airspace Study/Removal
846	Tree	623.7	632.2	-8.5	656.6	-32.9	668.5	-44.8	-	-	-	-	721.6	-97.9	No Action
847	Building	636.3	632.3	4.1	656.6	-20.3	-	-	-	-	-	-	-	-